

The background of the slide features a low-angle photograph of a tall telecommunications tower against a cloudy sky. Several large, thick, orange and dark blue curved lines are overlaid on the image, creating a sense of motion or signal waves. The TAWAL logo is positioned in the top left and bottom left corners.

TAWAL

TAWAL

MOP
Methode of Procedure

Document Control

Properties	Remark
TCN Summary	Site Survey
Site ID	ZTEST01
Name of Requester:	Mohammed Alhaj
Name of PM:	Abdulrahman Balfaqih
Site Impact (YES/NO)	NO - No Impact

TCN Justification and Summary

- TCN request for E1 survey & Quality checking of Sites
- Prepare the necessary tools
- No Impact

TCN Risk Details:

- Site Survey

Step by step Procedure:

1. Call TOC to open the TCN and confirm scope.
2. Post access notification on the Access Group.
3. Verify no active alarms on site with TOC.
4. Access site and confirm on-site team presence.
5. The Activity steps as below.
 - Check all Passive equipment at site
 - Check all site condition
 - Check the shelter from all point
 - Check the site fence area from all the points
 - **NOT ALLOWED** to check alarms at site during site survey (Only Door Alarms to be report).
6. Re-validate alarm status with TOC.
7. Close TCN with TOC sign-off.
8. Capture before/after photos and screenshots of configurations and logs.

Rollback Procedure

1. Rollback all actions done at site to the original status of the site.
2. Inform TOC of any unexpected issues.



3. Revert any changed configurations outside the approved scope.
4. Do not touch any equipment not covered by this TCN.

